



Model Number: SP-250-3-2 L2

Gillette SP-250-3-2 L2 Sentry Pro 25KW Standby Generator 208v 3 Phase 87 Amps Liquid Cooled Level 2 Quiet Series 1800 Rpm

Manufacturer: Gillette Generator

Gillette SP-250-3-2 Sentry-Pro Power Plants 25KW Standby Generator 240v 1 Phase 104 Amps Liquid Cooled Level 2 Quiet Series Enclosure 1800 Rpm

100% Quieter than most standby units

38% larger engine means unit is running with ease and last much longer (compare to 1.5 liter engines on competing units)

Heavy Duty Extra Large Air Cleaner

Level 2 Enclosure includes 1" X 4 lbs density foam throughout housing interior and includes air dams and "Critical" grade HD silencer.

(Compare to other liquid cooled brands, only included an enclosure - no foam!)

2.4 Liter PSI Engine/ 60 Hertz, HD Liquid cooled engine (Compare to light duty air cooled engine = less engine noise)

1800 Rpm (Compare to 3600 Rpm air cooled = quieter performance)

Operates on LPG or Natural Gas.

4-Pole Commercial / UL-2200 Certifies / Industrial Standby Sets

Includes:

Float Battery Charger, Silencer, flexible Oil and Radiator Drain Hose for easy

Maintenance, Programmable Digital Controller, Battery Tray and Cables,

Overload Circuit Breaker: 125 Amp / 240 Volt / Lug size 4-4/0

Optional

Part #

Part

Description

Price

S-10A

1" Flexible Dry Fuel Line

LPG or Natural Gas Line with 1" Npt fittings, 16" Long for 25-60KW

\$200

S-13C

1000 Watt Engine Coolant Heater

Coolant Heater with ON-OFF Thermostat. For 25-60KW

\$400

S-B600
600 CCA Starting Battery
12 VDC Starting Battery / 600 Cold Cranking Amps
\$200

S-17BC
Emergency Stop Switch Normally Closed
"Mushroom" style STOP Switch mounted in NEMA-4X UL Listed Enclosure /
Includes Clear Hinged Lift Cover
\$400

S-39
DC Enclosure Lights
12 VDC Powered LED Cavity Interior Enclosure Service Lighting
\$575

S-39AC
AC Enclosure Lights
120 VAC Powered LED Cavity Interior Enclosure Service Lighting (Electrical
Contractor to Supply Load Wires that are Circuit Protected from Building)
\$575

S-40
Liquid LP Fuel System
Complete Liquid LP Carburetion System Installed
\$1667

S-41A
Dual Fuel (LPG/NG) Automatic Fuel Switching
As one dry fuel source ends, the second connected dry fuel source
automatically continues nonstop operation! For 25KW - 150KW (Not available when
using the S-40 Liquid LP system)
\$2243

S-78A
Load Center
Auxiliary Connection Box Frame Mounted. 120/240 1Ph Terminal Strips Only
for Block Heater & Battery Charger Connection Upgrades. Electrical contractor
to supply load wires that are circuit protected from building.
\$564

S-MD24
Motorized Dampers
24"X24" HD 120-240 VAC Motorized Damper (Enclosure ventilation Control)
\$1667

S-112A
Enclosure Door Restraints
Service Door Restraints to hold doors open
\$552

S-114A
Isolator Mounting Pad
3"X6"X1/4" Thick Anti-Vibration Pads, 4 pack
\$225

S-EH3
Enclosure Space Heater
3 KW, 1 Phase or 3 Phase Heater (Consult Rep for Voltage &
Thermostat Requirements)
\$1580

ATSS13R-200-1-1
Service Entrance Rated Transfer Switch
UL-1008 Certified Entrance Rated 2&3 Pole Industrial ASCO 185 Series
Automatic Transfer Switch
\$2000

S-35A
Aluminum Skid Base
Separate, all aluminum bottom skid base, replacing standard steel skid 68"
base
\$2000

S-37A
Stainless Outer Housing
Replace Standard Housing with all exterior, brushed stainless steel housing
(perfect coastal accessory - looks cool too!)
\$2000

S-56
Winding Upgrade
Special winding insulation system consisting of (3) individual dips and bake
cycles of 100% solid varnish with final epoxy overcoat finish, plus fungus and

moisture spray protection
\$700

S-59
Winding Upgrade
Internal generator space heater, energized with 120/240 vac, keeping rotor
and stator winding dry in humid conditions, during standby operation
\$525

S-122A
R7 Foam Upgrade
Upgrade foam to 2" R7 Foam + Noiseless metal sound dampener in exhaust
chute. 4-5 dba additional sound reduction
\$1127

S-51A
Frame Drip Pan
Environmental Liquid Containment Pan Installed under frame base
\$750

Download Documents
SP-250 Specifications
SP-250 Level 2 Enclosure Line Drawings
SP-250 Level 3 Enclosure Line Drawings
SP-250 Open Line Drawing
180 mph windload calcs
SP-250 Submittal Pack
SP-250-EPA Certificate
ATS Choices
Circuit Breaker and Winding Upgrades
Silencer Upgrades
Controller Upgrades
Special Additional Feature for 1800 rpm

Availability: This product was added to our catalog on Saturday 27 March, 2021